

ALUMINUM BODY

MAXIMUM O.A.H. 140.00"

NOTE

DIMENSIONS SHOWN ARE APPROXIMATE AND ARE SUBJECT TO MINOR DEVIATIONS AS MAY OCCUR OR BE NECESSARY IN CONSTRUCTION.
MINOR DETAILS NOT SHOWN.

1. BATTERY CHARGER/AIR COMPRESSOR LOCATED IN CAB
2. S/STL PROTECTIVE GUARD FOR ROLL DOOR IN COMPARTMENT D1,D3,D4,D6,P1,P3,P4,P6,P7,R1
3. KEYED LOCKS FOR ROLL DOOR ON COMPARTMENT P1
4. PULL STRAP ON DOOR IN COMPARTMENT D3,D4,D5,D6,P3,P4,P5,P6
5. ONE ADJUSTABLE FULL WIDTH/DEPTH SHELF IN COMPARTMENT D1,P1
6. ONE ADJUSTABLE MAX WIDTH/DEPTH SLIDE-OUT TRAY (1/2 TRANSVERSE) IN COMPARTMENT D6,P6
7. ONE FLOOR MOUNTED FULL WIDTH/DEPTH SLIDE-OUT TRAY IN COMPARTMENT D1,D4,D6,P4,P6
8. ONE ADJUSTABLE TILT/SLIDE-OUT FULL WIDTH/DEPTH TRAY IN COMPARTMENT-D3,D4,P3;TWO IN P4,D6,P6
9. ONE ADJUSTABLE TOOL BOARD 2-WAY TRANSVERSE IN COMPARTMENT D6/P6
10. ALL BODY COMPARTMENTS WITH LOUVERS SHALL HAVE A REMOVABLE FILTER
11. FULL HEIGHT VERTICAL PARTITION IN TRANSVERSE COMPARTMENT D6/P6
12. FLOOR EXTENSION IN COMPARTMENT D6,P6
13. STABILIZERS MODIFIED FOR 18.00" GROUND PENETRATION
14. ONE ZICO AIR BOTTLE HOLDER WITH CRS MOUNTED WITH TRACKS IN COMPARTMENT 2
15. CIRCUIT BREAKER PANEL IN COMPARTMENT P6
16. AKRON ERWC-10-28 ELECTRIC REWIND CORD REEL WITH 200' OF 10/3 CABLE IN COMPARTMENT D4,P4
17. TWO 15A 120V SB DUPLEX RECEPTACLES LOCATED IN COMPARTMENT-P2,P4;TWO IN P6
18. L.E.D. LIGHTING ON AERIAL LADDER SECTIONS
19. 2-WAY INTERCOM SYSTEM BETWEEN AERIAL TIP AND TURNTABLE
20. NON-RAISED AERIAL PEDESTAL
21. AERIAL 14.00" LIMITED RETRACTION
22. SLIDE-OUT WORK SURFACE TRAY IN COMPARTMENT-D4,P1
23. LYFEPULLEY RESCUE SYSTEM AT AERIAL TIP

REV	DATE	BY	CH
V	17AUG16	JGA	LPA
V	11JUL16	BST	SHA
V	30JUN16	BST	SHA
V	11MAR16	RPA	JBL

CHASSIS DATA
MAKE PIERCE
MODEL VELOCITY

Pierce MANUFACTURING INC.

TITLE: 105 AERIAL LADDER & BODY ASSEMBLY NO TANK-NO PUMP

FOR: CONTRA COSTA COUNTY FIRE PROTECTION DISTRICT PLEASANT HILL, CA

DWG NO. 29770AD-SH1

JOB NO.	29770
SCALE 1:24	DATE
DRAWN BY JGA	23FEB16
CHECKED BY JBL	24FEB16
SHEET SIZE D	SHEET NO. 1 OF 2

View File Created 22-AUG-2016 12:07:23